

# TABLE OF CONTENTS

## SECTION 1 INTRODUCTION

1.1 Introduction. ....	1-1
1.2 Definitions.....	1-1
1.3 Bonds and Insurance.....	1-6
1.4 Starting and Completing the Work.....	1-6
1.5 Before Construction Begins.....	1-6
1.6 Preconstruction Conference .....	1-7
1.7 Approved Documents Intent .....	1-7
1.8 Amending and Supplementing the Approved Drawings .....	1-8
1.9 Underground Facilities Shown or Indicated .....	1-8
1.10 Underground Facilities Not Shown or Indicated.....	1-8
1.11 Reference Points and Monuments .....	1-8
1.12 Contractor's Responsibilities -Supervision and Superintendents.....	1-9
1.13 Safety and Protection .....	1-9
1.14 Site Emergencies .....	1-10
1.15 Authorized Variations in Work .....	1-10
1.16 Rejecting Defective Work .....	1-10
1.17 Warranty and Guarantee .....	1-11
1.18 Inspections and Observations .....	1-11
1.19 Contractor Employees .....	1-12
1.20 Historic, Archaeological or Paleontological Discoveries .....	1-12
1.21 Working Hours .....	1-12
1.22 Uncovering Work .....	1-12
1.23 City's Representative May Stop the Work .....	1-12
1.24 Correction or Removal of Defective Work by Contractor .....	1-13
1.25 One Year Correction Period .....	1-13
1.26 Acceptance of Defective Work.....	1-13
1.27 Correction or Removal of Defective Work by Owner .....	1-13
1.28 Work Fully Completed .....	1-13
1.29 Final Inspection .....	1-14
1.30 Final Walkthrough.....	1-14
1.31 Final Acceptance .....	1-14
1.32 Suspension of Work .....	1-14

## **SECTION 2 GENERAL REQUIREMENTS**

2.1	Introduction.....	2-1
2.2	Construction Drawings .....	2-1
2.2.1	General.....	2-1
2.2.2	Curb and Gutter, Drainage, Sidewalks and Streets .....	2-2
2.2.3	Sewer/Storm Sewer.....	2-3
2.2.4	Culinary Water.....	2-4
2.2.5	Secondary Water.....	2-4
2.2.6	Power .....	2-4
2.2.7	Detail Sheets .....	2-5
2.2.8	Grading Plan.....	2-5
2.2.9	General Utility Location Information.....	2-5
2.2.10	Drawing Submittals.....	2-7
2.3	Inspection, Testing and Quality Control. ....	2-7
2.3.1	Requests for Inspection. ....	2-7
2.3.2	Construction Completion Inspection (Final Inspection).....	2-7
2.3.3	Guarantee of Work .....	2-8
2.3.4	Quality Control Testing .....	2-8
2.3.5	Test Reports .....	2-9
2.4	Drawings of Record .....	2-9
2.5	Barricades and Warning Signs - Work Area Protection. ....	2-9
2.5.1	General Traffic Control Requirements .....	2-10
2.6	Cooperation with Utilities .....	2-11
2.7	Cooperation Between Contractors.....	2-12
2.8	Construction Stakes, Lines and Grades .....	2-12
2.9	Use of Explosives .....	2-13
2.9.1	Permits and Blast Plan .....	2-13
2.9.2	General Blasting Criteria.....	2-13
2.9.3	Logs.....	2-15
2.10	Protection and Restoration of Property and Landscape .....	2-15
2.11	Survey Monuments. ....	2-16
2.12	Hazardous Materials Discoveries .....	2-16
2.13	Improvement Sequence.....	2-17

## SECTION 3 DESIGN STANDARDS

3.1	General.....	3-1
3.2	Street Design.....	3-1
3.2.1	Street Cross-section Standards.....	3-1
3.2.2	Roadway Network Design .....	3-1
3.2.3	Improvement Requirements .....	3-4
3.2.3.1	Curb, Gutter and Sidewalk .....	3-4
3.2.3.2	Driveway's .....	3-4
3.2.3.3	Pavement .....	3-4
3.2.3.4	Street Lighting .....	3-4
3.2.3.5	Cross Gutters .....	3-4
3.2.3.6	Handicap Ramps .....	3-4
3.2.3.7	Roadway Medians.....	3-5
3.2.3.8	Minimum Access .....	3-5
3.2.3.9	Drainage.....	3-5
3.2.3.10	Traffic Control Devices .....	3-5
3.2.3.11	Pavement Marking .....	3-5
3.2.3.12	Street Trees & Landscaping .....	3-5
3.2.3.13	Other Improvements.....	3-5
3.2.4	Technical Design Requirements.....	3-5
3.2.4.1	Street Grades .....	3-5
3.2.4.2	Intersections .....	3-6
3.2.4.3	Intersection Spacing.....	3-8
3.2.4.4	Maximum Design Volume.....	3-8
3.2.4.5	Cul-de-sac Streets.....	3-8
3.2.4.6	Sidewalks .....	3-9
3.2.4.7	Curb and Gutter.....	3-9
3.2.4.8	Planter Strips.....	3-9
3.2.4.9	Design Speed.....	3-9
3.2.4.10	Clear Sight Distance at Intersections .....	3-10
3.2.4.11	Vertical Alignment .....	3-11
3.2.4.12	Safe Stopping Sight Distance.....	3-11
3.2.4.13	Horizontal Curves.....	3-12
3.2.4.14	Superelevation .....	3-12
3.2.4.15	Deceleration Lanes .....	3-12
3.2.4.16	Driveway Profiles.....	3-13
3.2.4.17	Alignment and Continuity - Off-site.....	3-14
3.2.5	Pavement Structural Design.....	3-14
3.2.6	Curb Side Mail Boxes .....	3-16
3.2.7	Signs and Pavement Markings .....	3-16
3.2.8	Underground Water .....	3-16
3.3	Soil Study Guidelines .....	3-16
3.3.1	Geotechnical Report.....	3-17
3.4	Drainage and Flood Control Design .....	3-19
3.4.1	General Requirements .....	3-19
3.4.2	Design Criteria - Streets .....	3-21

3.4.3	Design Criteria - Storm Drains .....	3-22
3.4.4	Design Criteria - Culverts.....	3-23
3.4.5	Design Criteria - Bridges.....	3-23
3.4.6	Design Criteria - Channels.....	3-24
3.4.6.1.	Open Channels .....	3-24
3.4.6.2.	Man-made Channels .....	3-24
3.4.6.3	Natural Channel .....	3-24
3.4.7	Design Criteria - Storage Facilities .....	3-24
3.4.7.1	Design Criteria.....	3-25
3.4.8	Floodplains .....	3-26
3.4.9	Erosion Control.....	3-26
3.4.10	Irrigation Ditches.....	3-27
3.4.10.1	Use of Ditches.....	3-27
3.4.10.2	Irrigation Company Approval.....	3-27
3.4.11	Water Quality Control.....	3-27
3.5	Sanitary Sewer Design .....	3-28
3.5.1	Design Flows .....	3-28
3.5.2	Minimum Size and Depth .....	3-29
3.5.3	Alignment.....	3-30
3.5.4	Service Connections.....	3-30
3.5.5	Manholes .....	3-31
3.5.6	Utility Clearances.....	3-32
3.5.7	Suspended Crossings .....	3-33
3.5.8	Pressure (Force) Mains .....	3-33
3.6	Culinary Water Design.....	3-34
3.6.1	Design Flow Pressure .....	3-34
3.6.2	Flow Design Criteria .....	3-35
3.6.3	Minimum Size and Depth .....	3-35
3.6.4	Valves and Hydrants .....	3-36
3.6.5	Pressure Reducing Valves .....	3-36
3.6.5.1	Secondary Pressure Reducing Valves .....	3-36
3.6.6	Fire Hydrant Spacing and Location .....	3-36
3.6.7	Fire Flow Requirements.....	3-37
3.6.8	Miscellaneous Water System Design Criteria.....	3-37
3.6.9	Network Hydraulic Analysis .....	3-39
3.6.9.1	When Required .....	3-39
3.6.9.2	Design .....	3-40
3.6.9.3	Submittal for Review and Approval .....	3-40
3.6.9.4	Miscellaneous.....	3-40
3.7	Secondary Water or Wastewater Reuse Irrigation System.....	3-41
3.8	Other Utilities Systems Design .....	3-41
3.8.1	Responsibility.....	3-41
3.8.2	Street Lights.....	3-41
3.8.3	Burial of Lines .....	3-41
3.8.4	Layout.....	3-42
3.8.5	Front Lot Line Systems.....	3-42

3.8.6	Quality Control .....	3-42
3.9	Traffic Standards .....	3-42
3.9.1	Access Control .....	3-42
3.9.1.1	General Requirements .....	3-42
3.9.2	Traffic Impact Studies .....	3-42
3.10	Survey Monumentation Standards .....	3-44
3.10.1	General Requirements .....	3-44
3.10.2	Monuments.....	3-45
3.10.3	Types of Monuments .....	3-46

## **SECTION 4 CONSTRUCTION STANDARDS**

4.1	Introduction.....	4-1
4.2	Survey Requirements .....	4-1
4.3	Earthwork .....	4-1
4.3.1	Materials .....	4-1
4.3.1.1	Excavation.....	4-1
4.3.1.2	Subsoil Reinforcement .....	4-1
4.3.1.3	Backfill .....	4-2
4.3.2	Construction Methods.....	4-2
4.3.2.1	Construction of Embankments .....	4-2
4.3.2.2	Compaction of Earth Materials .....	4-2
4.3.2.3	Subgrade Preparation. ....	4-3
4.3.2.4	Construction of Nonstructural Fills. ....	4-4
4.3.3	Quality Control.....	4-4
4.3.3.1	Testing.....	4-4
4.3.3.2	Acceptance.....	4-5
4.3.4	Special Requirements .....	4-5
4.4	Pipeline Construction.....	4-5
4.4.1	Materials.....	4-5
4.4.1.1	Sewer Pipe and Fittings.....	4-5
4.4.1.2	Storm Drain Pipe .....	4-7
4.4.1.3	Sewer Manholes .....	4-9
4.4.1.4	Water Pipe and Fittings .....	4-11
4.4.2	Construction Methods.....	4-20
4.4.2.1	Control of Ground Water .....	4-20
4.4.2.2	Excavation for Pipelines .....	4-21
4.4.2.3	Sheeting, Bracing, and Shoring of Excavations. ....	4-23
4.4.2.4	Blasting.....	4-23
4.4.2.5	Pipe Laying and Bedding. ....	4-23
4.4.2.6	Backfilling and Compaction .....	4-27
4.4.2.7	Trenches on Highways and Streets.....	4-31
4.4.2.8	Cleaning of Sanitary Sewer Lines .....	4-31
4.4.2.9	Cleaning and Disinfection of Water Systems.....	4-31
4.4.2.10	Special Requirements .....	4-32
4.4.3	Quality Control.....	4-33
4.4.3.1	Trench Backfill Moisture/density Testing .....	4-33

4.4.3.2	Sanitary and Storm Sewer Line Testing and Acceptance	.... 4-34
4.4.3.3	Water System Testing and Acceptance.....	4-37
4.5	Roadway Construction .....	4-38
4.5.1	General Requirements .....	4-38
4.5.2	Construction Staking .....	4-39
4.5.3	Grade Control Systems .....	4-40
4.5.4	Geotechnical Investigation.....	4-41
4.5.5	Roadway Subgrade .....	4-41
4.5.5.1	Preparation.....	4-41
4.5.5.2	Tolerances.....	4-43
4.5.6	Subbase - Class I and Class II. ....	4-43
4.5.7	Untreated Roadbase - One Inch and Three-quarter Inch .....	4-44
4.5.8	Prime Coat.....	4-46
4.5.9	Tack Coat .....	4-48
4.5.10	Dense-graded Asphalt.....	4-47
4.5.10.1	Related Work .....	4-49
4.5.10.2	Asphalt Cement.....	4-49
4.5.10.3	Shipment of Asphalt Material .....	4-50
4.5.11	Hydrated Lime for Asphalt Mixture .....	4-51
4.5.12	Aggregate .....	4-52
4.5.13	Storing, Mixing & Shipping of Plant Mix Bituminous Pavements ..	4-54
4.5.13.1	Storage.....	4-54
4.5.13.2	Batch Plant Method.....	4-54
4.5.13.3	Drier-drum Method .....	4-56
4.5.14	Asphalt Concrete Surge and Storage Silos .....	4-59
4.5.15	Shipping Asphalt Mixtures .....	4-59
4.5.16	Surface Preparation for Asphalt Overlays.....	4-60
4.5.17	Adjustment of Manhole and Utility Covers .....	4-60
4.5.18	Asphalt Paving Equipment.....	4-60
4.5.19	Rollers .....	4-62
4.5.20	Weather and Date Limitations .....	4-62
4.5.21	Spreading and Finishing.....	4-62
4.5.22	Rolling and Compacting.....	4-64
4.5.23	Open-graded Wearing Course.....	4-67
4.5.23.1	Wearing Course .....	4-67
4.5.23.2	Suitability of Aggregate .....	4-68
4.5.23.3	Mix Design .....	4-69
4.5.23.4	Mixing.....	4-69
4.5.23.5	Surface Placement.....	4-69
4.5.24	Acceptance Testing Requirements and Tolerances .....	4-70
4.5.24.1	Subbase .....	4-70
4.5.24.2	Roadbase and Recycled Aggregate Materials (RAM).....	4-71
4.5.24.3	Dense-graded Asphalt Pavements.....	4-72
4.5.24.4	Compaction of Dense-graded Asphalt Pavement .....	4-73
4.5.24.5	Open-graded Asphalt Wearing Course. ....	4-74
4.5.24.6	Asphalt Pavement Surfaces .....	4-74

4.6 Bituminous Seal Coat (Chip Seal) .....	4-75
4.6.1 Material Specifications.....	4-75
4.6.1.1 Bituminous Material.....	4-75
4.6.1.2 Aggregate (Chips) .....	4-75
4.6.2 Aggregate Quality Control .....	4-76
4.6.3 Equipment .....	4-77
4.6.3.1 Asphalt Distributor .....	4-78
4.6.3.2 Aggregate Spreader .....	4-78
4.6.3.3 Rollers .....	4-78
4.6.3.4 Dump Trucks .....	4-78
4.6.3.5 Front End Loaders .....	4-78
4.6.3.6 Power Brooms.....	4-79
4.6.4 Bituminous Chip Seal Construction Methods.....	4-79
4.6.4.1 Surface Preparation .....	4-79
4.6.4.2 Asphalt Application.....	4-79
4.6.4.3 Aggregate Spreading .....	4-80
4.6.4.4 Aggregate Compaction.....	4-80
4.6.4.5 Loose Aggregate Removal.....	4-81
4.6.4.6 Sanding .....	4-81
4.6.4.7 Appearance .....	4-81
4.6.4.8 Weather Limitations.....	4-82
4.7 Asphalt Emulsion Seal Coat (Slurry Seal) .....	4-82
4.7.1 Material Specifications.....	4-82
4.7.1.1 Asphalt Emulsion.....	4-82
4.7.1.2 Aggregate.....	4-82
4.7.1.3 Filler .....	4-82
4.7.1.4 Set Control Additive.....	4-83
4.7.1.5 Water.....	4-86
4.7.2 Material Quality Control .....	4-86
4.7.2.1 Sampling and Testing.....	4-86
4.7.2.2 Job Mix Design.....	4-86
4.7.3 Equipment .....	4-87
4.7.3.1 Slurry Mixing Machine .....	4-87
4.7.3.2 Slurry Spreader .....	4-87
4.7.3.3 Surface Cleaning Equipment.....	4-88
4.7.3.4 Auxiliary Equipment.....	4-88
4.7.4 Asphalt Emulsion Slurry Construction Methods.....	4-88
4.7.4.1 Resident Notification .....	4-88
4.7.4.2 Vehicle Removal .....	4-88
4.7.4.3 Preparation of Surface .....	4-88
4.7.4.4 Cleaning Streets.....	4-88
4.7.4.5 Sewer Manhole Lids and Water Valve Covers .....	4-89
4.7.4.6 Test Section .....	4-89
4.7.4.7 Water Fog .....	4-89
4.7.4.8 Preparation of Slurry .....	4-89
4.7.4.9 Application of Slurry .....	4-90

4.7.4.10. Handwork.....	4-90
4.7.4.11. Joints.....	4-90
4.7.4.12. Curing.....	4-90
4.7.4.13. Weather Limitations.....	4-91
4.8 Concrete Work.....	4-91
4.8.1. Materials.....	4-91
4.8.1.1 Portland Cement Concrete Material .....	4-91
4.8.1.2 Concrete Reinforcing Materials.....	4-99
4.8.1.3 Curb, Gutter, Sidewalk and Base Materials.....	4-101
4.8.2. Construction Methods and Equipment.....	4-101
4.8.2.1 General Concrete Placement .....	4-101
4.8.2.2 Concrete Reinforcement Installation .....	4-104
4.8.2.3 Curb, Gutter and Sidewalk Concrete Placement. ....	4-105
4.8.2.4 Concrete Base Materials Placement. ....	4-109
4.8.3. Quality Control.....	4-109
4.8.3.1 Concrete Testing .....	4-109
4.8.3.2 Concrete Base Material Testing .....	4-110
4.8.3.3 Acceptance.....	4-110
4.9 Restoration of Existing Surface Improvements. ....	4-111
4.9.1 Introduction.....	4-111
4.9.2 Gravel Surfaces.....	4-111
4.9.3 Bituminous Surfaces.....	4-112
4.9.4 Concrete Surfaces.....	4-113

## **SECTION 5 SIGNING AND PAVEMENT MARKINGS**

5.1 Introduction.....	5-1
5.2 Signing Materials, Fabrication and Placement.....	5-1
5.2.1 Street Name Signs .....	5-1
5.2.2. Traffic Signs.....	5-1
5.2.3 Visibility.....	5-1
5.3 Pavement Markings.....	5-1
5.3.1 Line Types.....	5-2
5.3.2 Pavement Word and Symbol Markings .....	5-2
5.3.3 Traffic Paint .....	5-2
5.3.4 Temporary Markings.....	5-3
5.3.5 Raised Pavement Markers .....	5-3

## **SECTION 6 STREET LIGHTING**

6.1 Introduction.....	6-1
6.2 Streetlight Pole .....	6-1
6.3 Policy “Street Lights and Security Lights” .....	6-1

## **SECTION 7 POWER SYSTEM**

7.1 Introduction.....	7-1
7.2 Electrical Services .....	7-1
7.2.1 Power Connection .....	7-1

7.2.2 Electric Service Agreement .....	7-1
7.2.3 Customer Service Facilities .....	7-1
7.3 Materials and Workmanship .....	7-2
7.4 Control of Ground Water.....	7-2
7.5 Excavation and Backfill.....	7-2
7.5 Concrete.....	7-3
7.7 Meters .....	7-3

## LIST OF TABLES

Table 3.1	Street Cross-section Configurations .....	3-3
Table 3.2	Facility Type- Access Distance From Corner .....	3-7
Table 3.3	Design Speed.....	3-10
Table 3.4	Sight Distance at Intersections .....	3-10
Table 3.5	Safe Stopping Sight Distance.....	3-11
Table 3.6	Horizontal Curves.....	3-12
Table 3.7	Driveway Type and Adjacent Street Classification .....	3-13
Table 3.8	Street and Gutter Capacity .....	3-21
Table 3.9	Sanitary Sewer Design Flows.....	3-28
Table 3.10	Sanitary Sewer Minimum Slopes.....	3-29
Table 3.11	Sanitary Sewer Laterals .....	3-31
Table 4.1	Sewer Pipe Dimensions .....	4-6
Table 4.2	General Pipe Requirements .....	4-12
Table 4.3	Corporation Stops .....	4-16
Table 4.4	Meter Box and Lid Size .....	4-17
Table 4.5	Backfill Material .....	4-22
Table 4.6	Air Testing .....	4-35
Table 4.7	Exfiltration Test.....	4-36
Table 4.8	Minimum Roadway Structural Requirements .....	4-42
Table 4.9	Subbase Aggregate Gradation .....	4-44
Table 4.10	Roadbase Aggregate Gradation.....	4-46
Table 4.11	Paving Grade Liquid Asphalt Requirements.....	4-50
Table 4.12	Marshall Design Requirements .....	4-52
Table 4.13	Dense-graded Asphalt Aggregate Gradation.....	4-53
Table 4.14	Climate Limitations .....	4-62
Table 4.15	Open-graded Asphalt Aggregate Gradation .....	4-67
Table 4.16	Rubberized Liquid Asphalt Requirements .....	4-68
Table 4.17	Sieve Size and Deviation.....	4-71
Table 4.18	Sieve Size and Deviation.....	4-72
Table 4.19	Bituminous Material.....	4-75
Table 4.20	Gradation of Aggregate for Chip Seal Coats .....	4-76
Table 4.21	Slurry Seal Test Specifications - Tests of Emulsions .....	4-83
Table 4.22	Slurry Seal Test Specifications - Tests of Residue.....	4-84
Table 4.23	Slurry Seal Test Specifications - Tests on Slurry Seal Job Mixture .....	4-85
Table 4.24	Slurry Mixture Gradation.....	4-86
Table 4.25	Fine Aggregate.....	4-92
Table 4.26	Fine Aggregate Gradation Requirements .....	4-92
Table 4.27	Course Aggregate .....	4-94
Table 4.28	Course Aggregate Gradation Requirements .....	4-94
Table 4.29	Concrete Mix Specifications .....	4-99
Table 4.30	Synthetic Reinforcing Fibers.....	4-100
Table 4.31	Reinforcing Bar Clearance .....	4-105